

Greater Fox Cities Area Habitat for Humanity 2020 Roofing Bid Specs

(Labor, tools and nails, only)

Proposal will be for the following labor (scope of work)

- Install all drip edge and gutter apron
- Provide kick out flashing as required on step flashing ends
- Install galvanized tin and ice and water shield on all valleys
- Apply ice and water shield on all eave ends (**2 rolls width each side**)
- Apply 15lb felt over entire roof
- Apply shingles using best practices
- Install ridge vent and cap shingles (includes garage and porch)
- Provide written warranty (labor only if applicable)
- Install fall protection strapping 10' from edge

Provide the following costs per square price for the above.

A date will be given at least two weeks in advance as to when house will be ready, roof must be completed within three working days of that date to facilitate rough in schedule. There is always a large generator on site for power.

All contractors must comply with all OSHA regulations, and especially all that relate to fall protection. If it is noticed that a contractor is working outside of these regulations they will be told to leave the site.

All contractors are required to comply with Habitat for Humanity recycling procedures. A copy of these procedures is included with this RFP.

All replies must be received by **January 20, 2020** to be considered.